



1565 Chenault Street, Dallas, Texas 75228

February 24, 2026

Office of Hopkins County Judge
PO BOX 288
Sulphur Springs, Texas 75483

**Underground Parallel &/OR Crossing(s)
Project PID 3540239 MV19E**

Greetings,

Spectrum/Charter is requesting permission to construct and placement of underground conduit and fiber. This request is for proposed construction on county road CR 3506 which is located in Hopkins County, Texas.

Site location map and google plans are enclosed. The construction plans detail the proposed work.

If you have any questions, please contact me at any time.

Sincerely,

Matt McClannon

Project Coordinator
Matt.mcclannon@charter.com
Phone 214-551-1196

Submitted by:
Dayna LaPoma / Kylie Lindsay
Project Coordinator / RDOF Coordinator
Dayna.lapoma@dfw-telecom.com
Kylie.Lindsay@dfw-telecom.com

Enclosures


County Approval Section:

Approved: 

Denied: _____

Authorized Signature: 

Date: 3-4-2026




Hopkins County Notes: Bore only no trenching and the conduit placement should be the backside of ditch away from the county road when running parallel to the CR


Project consist of approximately:
535' of Underground fiber

GENERAL CONSTRUCTION NOTES

- ALL CONSTRUCTION WORK WITHIN THE PUBLIC RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH THE ORDINANCES AND REGULATIONS OF THE MUNICIPALITY IN WHICH THE WORK IS TO BE PERFORMED.
- EXISTING UTILITY LOCATIONS: WORKS ARE TAKEN FROM AVAILABLE RECORDS AND MAY NOT BE ALL INCLUSIVE. UTILITY LOCATIONS ARE GENERALLY SCHEMATIC IN NATURE AND MAY NOT ACCURATELY REFLECT THE SIZE AND LOCATION OF EACH PARTICULAR UTILITY. THE CONSTRUCTION CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR VERIFYING THE LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR IDENTIFYING THE EXISTING UTILITIES AND THE PROTECTION OF ALL EXISTING FACILITIES BEFORE SHOWN OR NOT SHOWN. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR REPAIRS TO ANY EXISTING FACILITY DAMAGED BY A DIRECT RESULT OF THE CONSTRUCTION ACTIVITIES. WHETHER THE FACILITY IS SHOWN ON THE DRAWINGS OR NOT.
- THE CONSTRUCTION CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL DEPARTMENTS WITHIN THE MUNICIPALITY AND THE UTILITY COMPANIES AT LEAST TWO WORKING DAYS PRIOR TO THE COMMENCEMENT OF WORK.
- CALL BEFORE YOU DIG
811
IT'S THE LAW
- IT SHALL BE THE RESPONSIBILITY OF THE CONSTRUCTION CONTRACTOR TO ATTEMPT DAMAGE TO PRIVATE AND PUBLIC PROPERTY BY RESTORE ALL AREAS EFFECTED BY THE CONSTRUCTION TO ORIGINAL OR BETTER CONDITION.
1. ALL BARRICADEING AND TRAFFIC CONTROL SHALL BE THE RESPONSIBILITY OF THE CONSTRUCTION CONTRACTOR AND SHALL CONFORM TO THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES. TRAFFIC FLOW AND ACCESS SHALL BE MAINTAINED DURING ALL PHASES OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TRAFFIC SAFETY MEASURES FOR WORK ON THE PROJECT. THE WORK SITE SHALL BE SUITABLY MARKED AND BARRICADED AT NIGHT.
2. THE CONSTRUCTION CONTRACTOR SHALL ABIDE BY ALL APPLICABLE FEDERAL, STATE AND LOCAL LAWS GOVERNING EXCAVATION. THE CONSTRUCTION CONTRACTOR SHALL PROVIDE ALL FRESH SAFETY SURVEILLANCE, WITH ALL LAWS GOVERNING EXCAVATION. THE CONSTRUCTION CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL ASPECTS OF WORK RELATED TO EXCAVATION.
3. ALL CONCRETE USED IN ANY REMEDIATION SHALL BE IN COMPLIANCE WITH THE SPECIFIED CLASSES OF CONCRETE IN THE STANDARD SPECIFICATIONS FOR PORTLAND CEMENT CONCRETE. FIVE (5) TOLLS OF CONCRETE IS SPECIFIED BY THE SPECIFICATION TO THE NORTH TEXAS TOLLS. STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION. 2004. ALL OTHER CONCRETE SHALL BE CLASS A CONCRETE.
4. ALL REINFORCING STEEL AND BOWLS BARS IN PAVEMENT SHALL BE SUPPORTED AND MAINTAINED AT THE CORRECT CLEARANCES BY THE USE OF BAR CHAINS OR OTHER APPROVED SUPPORT.
5. ALL CONCRETE MUST BE PLACED WITH A MINIMUM 4" OF COVER UNLESS OTHERWISE SPECIFIED.
6. ALL BARRICADEING WILL BE MECHANICALLY TAMPED IN LOTS TO A DENSITY OF 95% GROSS. THE REQUIRED DENSITY WILL BE OBTAINED BY USING TAMPERS. TAMPERS OF ROLLING EQUIPMENT LOTS MAY VARY ACCORDING TO THE TYPE OF EQUIPMENT USED TO OBTAIN THE REQUIRED DENSITY. SAND AND DEBRIS FREE MATERIAL WILL BE USED FOR BARRICADE.



UNDERGROUD CONDUIT 1-2" HDPE



PREPARED BY: DFW TELECOM, INC



1565 Chenault St | Dallas, TX 75228

February 25, 2026

Office of Hopkins County Judge
PO BOX 288
Sulphur Springs, Texas 75483

**65' UG bore & conduit placement
Project PID 6569998**

Greetings,

Spectrum/Charter is requesting permission to construct and placement of underground conduit and fiber. This request is for proposed construction on county road CR 4759 which is located in Hopkins County, Texas.

Site location map and Google plans are enclosed. The construction plans detail the proposed work.

If you have any questions, please contact me at any time.

Sincerely,

Luis Calderon
Construction Supervisor
luis.calderon@tcscomm.com
Phone 303-518-8341

Submitted by:
Suzanne Hamm
Project Coordinator
Suzanne.Hamm@tcscomm.com

Signature: SH0407

Digitally signed by SH0407
DN: cn=Suzanne.Hamm@tcscomm.com, o=Charter, ou=Standard
Business, ou=TCs, ou=Company, ou=Hopkins, ou=Hopkins
Date: 2026.02.25 08:13:11 -0800

County Approval Section:

Approved:

Denied:

Authorized Signature:

Date: 2-3-26

